

BANGALORE DIVISION.

Dated 6th May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 25th May 1929, for constructing Mysore State Life Insurance Office Building at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3a. Percentages less or above will not be accepted.

4. Each tender must be accompanied by a deposit of rupees two thousand and five hundred in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing Mysore State Life Insurance Office Building" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

General abstract of the estimate for the construction of Mysore State Life Insurance Office Building in Bangalore.

No.	Items of work	Per	Ground floor		First floor	
			Quantity	Rate	Quantity	Rate
				Rs.		Rs.
1	Earthwork excavation and filling in basement	C.yd.	2,330		...	
2	Stone jelly concrete in mortar ...	C.ft.	17,953		...	
3	Burnt size stones in mortar with bond slabs at intervals.	"	41,336		...	
4	Burnt stone in mortar superstructure with bond slabs at intervals.	"	25,242		...	
5	Burnt brick in mortar ...	"	...		21,179	
6	Burnt stone slabs 4" to 6" thick including fixing and hoisting charges.	S.ft.	2,327		1,964	
7	Burnt stone slabs 6" thick with chamfered edges and fixing charges.	"	1,891		...	
8	Two line dressing to burnt stone slabs ...	"	1,134		...	
9	Three line dressing to cill slabs of windows ...	"	96		192	
10	Burnt stone in mortar arch work ...	C.ft.	4,485		...	
11	Burnt brick in mortar arch work ...	"	...		2,300	
12	Burnt brick in mortar round semi circular pillars (6' x 1 dr.) with base and capital with one circular bond stone slab in the centre with plastering, etc., complete.	Each	...		88	

Serial No.	Items of work	Per	Ground floor		First floor	
			Quantity	Rate	Quantity	Rate
13	Burnt brick in mortar round pillars 1' thick at bottom with ornamental base and capital with flute work plastering, etc., complete as per design with two bond slabs for each pillar cut to the shape 13' height.	Each	...		9	
14	Do do do do $\frac{1}{4}$ and $\frac{3}{4}$ pillars	"	...		20	
15	Providing teak wood doors 4" x 5" frame $1\frac{1}{2}$ " thick shutters $\frac{1}{3}$ panelled at bottom $\frac{2}{3}$ glazed at top including rectangular swing top ventilator with necessary iron fittings, double brass knots, etc., complete.	S ft.	2515		2412	
16	Providing teak wood windows in teak frames 4" x 5" with $\frac{3}{4}$ " iron bars, $1\frac{1}{4}$ " thick glazed shutters inside $1\frac{1}{4}$ " thick panelled shutter outside with iron fittings, etc., complete.	"	320		320	
17	Providing teak wood semi circular ventilator with 4" x 5" frame and swing glazed shutters, rings, etc., complete.	"	567		402	
18	Providing teak wood semi-circular ventilator frames 4" x 5" with fixed ornamental glazed shutter as per design.	"	25		25	
19	Steel girders and joist including lifting and hoisting charges.	Cwt.	558.2		700	
20	Roofing with jac arched terrace as per specification.	Sqr.	117.60		116.49	
21	Chunam plastering Stone wall	"	344.63			
22	Do Brick wall	"	...		383.32	
23	Flooring with Marceilles tiles over mortar bed laid diagonally with border tiles and cement pointing complete.	"	48.94		100.00	
24	Flooring with 1' square shaban slabs over 3" concrete laid diagonally with border slabs and cement pointing complete.	"	41.24		...	
25	Flagging the portico with $1\frac{1}{2}$ " square burnt stone slabs laid diagonally with border slabs over 3" concrete bed and cement pointing.	S.ft.	644		...	
26	Ornamental cast iron railing as per design with wooden top rail fixed in position between pillars with necessary.	R.ft.	...		372	
27	Ornamental work as per design in the portico entablature.	"	...		79 $\frac{1}{2}$	
28	Ornamental panelling for the frontage as per design with inscriptions.	Each	...		1	
29	Cornice dental $1\frac{1}{2}$ '	R.ft.	316		312 $\frac{1}{2}$	
30	Ordinary cornice work $1\frac{1}{2}$ '	"	432		429	
31	Parapet wall burnt brick in chunam $3\frac{1}{2}$ ' in height with base 1' x 12" and wall 1' thick with top cornice plastering, etc., complete.	"	...		291 $\frac{1}{2}$	
32	Parapet wall burnt brick in chunam $2\frac{1}{2}$ ' in height with base 1' x 9" and wall 9" thick with top cornice plastering, etc., complete.	"	...		429	
33	Masonry finials as per design	Each	...		4	
34	Providing cast iron down pipes 3" x 4" with necessary bends, mouths at top and fixture.	R.ft.	1364		792	
35	Providing expanded metal for the gutters at top with necessary cement plastering.	Each	...		44	
36	Masonry drain 9" x $1\frac{1}{2}$ ' ventway in brick in mortar 9" thick side walls U shaped with jelly concrete bedding, cement plastering inside with top covering slab including necessary excavation and refilling.	R.ft.	800		...	

No.	Items of work	Per	Ground floor		First floor	
			Quantity	Rate	Quantity	Rate
				Rs.		Rs.
37	Binding wall over terrace $1\frac{1}{2}' \times 1\frac{1}{2}'$ top rounded with brick in mortar and plastered alround.	R.ft.	...		661	
38	Cornice work 3" above the crown of arch ...	"	748		741	
39	Do 6" for the arches ...	"	630		518	
40	Crown mouldings ...	Each	55		44	
41	Cornice work 6" at the springing of arch ...	R.ft.	716		336	
42	Triangular moulding with vertical shafts at sides for windows outside as per design complete.	Each	...		8	
43	Panel work in front of windows with shafts outside for windows outside as per design complete.	Each	8		...	
44	Silicate painting 2 coats ...	Sqr.	149.98		170.51	
45	Stair case with necessary teakwood posts sides $2\frac{1}{2}"$ thick trad $1\frac{1}{4}"$ thick rise 1" thick planks wrought and put up with two coats of varnishing as per design with bottom planks $\frac{1}{2}"$ thick.	"	229½		...	
46	Providing ornamental cast iron railing with necessary teakwood had rail at top newel post with painting and varnishing.	R.ft.	60		...	
47	Cement pointing to basement alround ...	Sqr.	21.93		...	
48	Cutting grooves in plaster alround outside ...	"	80.00		...	
49	White and colour washing 2 coats ...	"	344.63		383.32	
50	Clearing site and levelling the ground ...	L. S.	...		...	
51	Forming the road with metalling and tarring ...	S.yd.	1,400		...	
52	Unforeseen charges ...	L. S.	...		...	

H. R. VENKATASUBBA RAO,
Executive Engineer.

THE BANK OF MYSORE, LIMITED, BANGALORE.

Statement of the affairs of the Bank of Mysore, Limited, for the week ending 2nd May 1929, published under Article 141 of the Articles of Association.

LIABILITIES		ASSETS	
	Rs.		Rs.
To Capital Receipts ...	20,00,000	By Cash in Hand and at Bankers	15,18,834
" Reserve Funds ...	17,00,000	" Loans and Cash Credit Accounts	163,88,931
" Public and other Deposits ...	204,89,920	" Bills discounted...	4,96,889
" Sundries ...	12,02,739	" Investments ...	62,78,068
(Annas and pies omitted.)		" Balance at Agencies	1,175
		" Dead Stock ...	5,81,829
		" Sundries ...	1,26,933
Total ...	Rs. 253,92,659	Total ...	Rs. 253,92,659

BANGALORE,
Dated 7th May 1929.

P. W. O'BRIEN,
Manager.